

Florence Gardens Phases IV and V

Special Provisions

Prepared For:



Prepared by:



2045 S. Vineyard Avenue
Suite 101
Mesa, Arizona 85210

All work performed shall comply to the latest edition of the MAG Uniform Standard Specifications except as listed below.

AMENDMENTS TO MAG STANDARD SPECIFICATIONS

SECTION 350 REMOVAL OF EXISTING IMPROVEMENTS

This section is modified to add:

350.4 Payment

Payment for removal of existing pavements, concrete, curb and gutter, and barricades will be made at the unit proposal price, which price shall include full removal of the items, any equipment and labor necessary, and disposal of items off site.

No separate measurement or payment will be made for removal of, or adjustments to, existing miscellaneous landscaping (e.g. granite, rocks) adjacent to new pavement edge, as such work is considered incidental to the pavement installation.

Add the following Section:

SECTION 351 RELOCATE EXISTING STREETLIGHT

351.1 Description

The work shall consist of relocating existing streetlights and installing new electrical conduit along Colorado Avenue to the proposed locations as shown on the project plans.

351.2 Materials

Electrical conduit shall be 3" in diameter.

351.3 Construction Methods

No as-builts for the streetlights are available, however field reviews indicate the streetlights are direct bury. Contractor shall verify existing method of installation prior to relocation.

Contractor shall contact the San Carlos Irrigation Project (SCIP) at 520-723-6212 at least five (5) working days prior to relocation to coordinate and schedule a disconnect and rewiring of the lights.

Conduit shall be installed to allow for re-wiring of the streetlights by SCIP. Exact limits shall be coordinated with SCIP representatives.

Trenching and backfill for conduits shall meet the depth requirements and specifications of SCIP.

351.4 Measurement and Payment

Relocation of the streetlights shall be paid at the contract unit price per each relocation and shall include all necessary equipment, conduit, trenching, excavation, backfill, labor, and concrete foundation if required.

No additional payment shall be made for coordination with adjacent property owners, the Florence Gardens HOA, the Town of Florence, or the San Carlos Irrigation Project as such is considered incidental to the bid price.